




F



5 Column Cap Detail
3" = 1'-0"




3 Tile @ Drain
3" = 1'-0"




1 Tile Transition @ 1x6 Boards
3" = 1'-0"

E




4 Typ. Tile at Corner
3" = 1'-0"




2 Tile Transition @ Base
3" = 1'-0"

D


I



LOUVER SCHEDULE



WINDOW SCHEDULE



DOOR ELEVATIONS

FRAME TYPES

DOOR SCHEDULE																		
NUMBER	TO	FROM	DOOR							FRAME TYPE	FRAME		FIRE RATING	HW SET	HEAD	JAMB	SILL	REMARKS
			CNT	WDTH	HGT	THK	TYPE	MAT'L	FINISH		MAT'L	FINISH						
100	MEN	BREEZEWAY	1	36"	84"	1 3/4"	A	ALUM	FACT	F2	ALUM	FACT		1a	H2	J2	S2	1
101	JAN./STORAGE	PORCH	1	36"	84"	1 3/4"	A	ALUM	FACT	F2	ALUM	FACT		2	H2	J2	S2	1
101A	ELEC.	JAN./STORAGE	1	24"	80"	1 3/4"	A	HM	PAINT	F1	HM	PAINT		3	H1	J1	S1	
102	FAMILY	PORCH	1	36"	84"	1 3/4"	A	ALUM	FACT	F2	ALUM	FACT		1b	H2	J2	S2	1
103	JAN./STORAGE	CHASE	1	24"	80"	1 3/4"	A	HM	PAINT	F1	HM	PAINT		3	H1	J1	S1	
104	WOMEN	BREEZEWAY	1	36"	84"	1 3/4"	A	ALUM	FACT	F2	ALUM	FACT		1a	H2	J2	S2	1
105	CHASE		1	24"	84"	1 3/4"	A	ALUM	FACT	F2	ALUM	FACT		2	H2	J2	S2	1

DOOR ABBREVIATIONS				DOOR REMARKS														
ALUM	ALUMINUM	FACT	FACTORY FINISH	1. WEATHERSTRIP FRAME TOP AND BOTH JAMBS AND INSTALL SWEEPSTRIP WEATHER BARRIER AT BOTTOM AS SPECIFIED.														
HM	HOLLOW METAL	PAINT	PAINTED FINISH															

DOOR GENERAL NOTES

A. DOORS AND DOOR HARDWARE TO BE ADA COMPLIANT WITH LOCAL BUILDING & FIRE CODES.

B. SEE FLOOR PLANS AND PARTITION TYPES FOR THROAT DEPTHS

C. UNDERCUT DOOR TO CLEAR TOP OF FLOOR FINISHES BY 1/4", U.O.N.

D. LOCK CORES TO BE COMPATIBLE WITH BUILDING STANDARD CYLINDERS AND KEYED TO MASTER SYSTEM. COORDINATE WITH OWNER.

E. ALL SINGLE DOORS TO RECEIVE 1-1/2" PAIR BUTT HINGES.

F. THE HARDWARE SET IS FURNISHED AS INFORMATION AND AS GUIDE ONLY, THE COMPLETE QUANTITY REQUIREMENTS FOR EACH OPENING SHALL BE THE RESPONSIBILITY OF GC.

C

B

A