

4/2/2024 4:58:07 PM

E

D

C

B

A

Table with columns: DESCRIPTION, MOUNTING HEIGHT (TO CENTER OF BOX), DRAWING SYMBOL, DESCRIPTION, MOUNTING HEIGHT (TO CENTER OF BOX), DRAWING SYMBOL, DESCRIPTION, MOUNTING HEIGHT (TO CENTER OF BOX), DRAWING SYMBOL, DESCRIPTION, MOUNTING HEIGHT (TO CENTER OF BOX), DRAWING SYMBOL, DESCRIPTION, MOUNTING HEIGHT (TO CENTER OF BOX), DRAWING SYMBOL.

Table with columns: DESCRIPTION, MOUNTING HEIGHT (TO CENTER OF BOX), DRAWING SYMBOL, DESCRIPTION, MOUNTING HEIGHT (TO CENTER OF BOX), DRAWING SYMBOL, DESCRIPTION, MOUNTING HEIGHT (TO CENTER OF BOX), DRAWING SYMBOL.

GENERAL NOTES (LEGEND):
A. EACH CONTRACTOR, PROPOSER, SUPPLIER AND/OR MANUFACTURER SHALL REFER TO ALL DOCUMENTS PERTAINING TO THIS PROJECT AND COORDINATE ACCORDINGLY SO AS TO ENSURE ADEQUACY OF FIT...

Wake County Public School System logo, LSP logo, CMTA logo, Steve E. Roby Professional Engineer seal, Swift Creek Elementary School address, LSP PROJECT: 6201-207411, BID SET SUBMISSION: 2024.04.10, SHEET: E00.01, BID SET: 2024.04.10



THESE DIMENSIONS ARE APPROXIMATE. VERIFY DIMENSIONS AND QUANTITIES FROM FLOOR PLANS.

E

D

C

B

A

4/30/2024 3:56:12 PM

LUMINAIRE SCHEDULE

Table with columns: TYPE, Count, DESCRIPTION, MANUFACTURER, BASIS OF DESIGN, EQUAL MANUFACTURERS, MOUNTING, LAMPS / CCT, MINIMUM LUMENS, MAXIMUM WATTAGE, VOLTAGE, REMARKS. Rows include various luminaire models like A4, A5, A6, A7, A10, B4, C3, C4, C5, D6-1, D6-2, D6-7, K5, LR4-6, LS2-6, LS2-8, ODR1, ODR2, ODS1, OP1, OP2, OWP2, P6, S4, T1, TR, V4, VP2, VP4, W4, X1, X2.

ELEC - EQUIPMENT CONNECTION SCHEDULE

Table with columns: EQUIP ID, DESCRIPTION, DISCONNECT MEANS, VOLTAGE, POLES, HP, POWER (KVA), MCA. Rows include equipment like AC-1, AC-2, AHU-1 through AHU-8, B-1, B-2, CH-1, CH-2, CU-1, CU-2, CUH-1, DP-1, EF-1 through EF-21, HP-1, HP-2, KEF-1, KILN, KILN FAN, PCHWP-1, PCHWP-2, RF, RH, SCHWP-1, SCHWP-2, SHWP-1, SHWP-2, TSP, UH-1, UH-2, VAV-XFMR, WH-1.

GENERAL NOTES (LUMINAIRE SCHEDULE):

- A. ALL LUMINAIRES AND COMPONENTS SHALL BE UL LISTED.
B. WHERE LUMINAIRES ARE SHOWN SPLIT-WIRED (HALF EMERGENCY POWER/HALF NORMAL POWER) ON FLOOR PLANS...
C. PROVIDE BALLASTS FOR FIXTURE LAMP SWITCHING AS INDICATED ON LIGHTING FLOOR PLANS...
D. CONTRACTOR SHALL FOCUS, AIM AND ADJUST LUMINAIRES UNDER THE SUPERVISION AND DIRECTION OF THE ENGINEER AND ARCHITECT...
E. ALL LAY-IN FIXTURES SHALL BE PROVIDED WITH SCREW ON HOLD DOWN CLIPS AND MAXIMUM 6'-0" LONG FLEXIBLE CONDUIT WHIPS...
F. EXIT SIGNS AND FIXTURES THAT ARE HATCHED OR WHERE THE FIXTURE TYPE CONTAINS THE SUFFIX "E" FOR EMERGENCY OPERATION SHALL HAVE AN INTEGRAL 90 MINUTE BATTERY INVERTER IF NOT POWERED FROM AN EMERGENCY GENERATOR...
G. ALL BATTERY POWERED FIXTURES SHALL HAVE TEST SWITCHES FACTORY INSTALLED INTEGRAL TO THE REFLECTOR. REMOTE TEST SWITCHES WILL NOT BE ACCEPTED.



Wake County Public School System



434 FAYETTEVILLE STREET SUITE 1700
RALEIGH, NORTH CAROLINA 27601
TEL. 919.829.2730 FAX. 919.829.2700
WWW.LS3P.COM



04/10/2024
COPYRIGHT 2024. ALL RIGHTS RESERVED. PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

Swift Creek Elementary School
5601 Tryon Rd Raleigh, NC 27606

Table with columns: DATE, DESCRIPTION. Multiple empty rows for notes.

SHEET NAME: ELECTRICAL SCHEDULES

BID SET SUBMISSION: 2024.04.10

SHEET: E00.02

BID SET



DATE	DESCRIPTION

Classified by Underwriters Laboratories, Inc. to ANSIUL 1479 (ASTM E814) and CANULC S115 System No. C-AJ-3317

ANSI/UL1479 (ASTM E814)	CANULC S115
F Rating - 3 Hr	F Rating - 3 Hr
T Ratings - 0 and 2 Hr (See Items 4 and 5)	FT Ratings - 0 and 2 Hr (See Items 4 and 5)
	FH Rating - 3 Hr
	FTH Ratings - 0 and 2 Hr (See Items 4 and 5)

3. **Through Penetrant Product - Flexible Metal Piping** - As an alternate to Item 3, one nom 2 in. (51 mm) diam (or smaller) flexible steel pipe (with or without plastic jacketing) to be installed either concentrically or eccentrically within the firestop system. The annular space between the pipe, conduit or tube and the periphery of the opening shall be min 0 in. (0 mm or point contact). The max annular space is 1 or 2 in. (25 or 51 mm) as shown in the table in item 4B. Pipe to be rigidly supported on both sides of the floor or wall assembly.

**OMEGA FLEX INC**  
**GASITTE, DIV OF TITFLEX**  
**WARD MFG L L C**

4. **Firestop System** - The firestop system shall consist of the following:

A. **Packing Material** - When required as shown in the table in Item 4B, min 4 pcf (64 kg/m<sup>3</sup>) mineral wool batt insulation, compressed and tightly packed to min 2-1/4 in. (57 mm) thickness. Packing material recessed from top surface of floor or both surfaces of wall as required to accommodate fill material (Item 4B). When packing material is shown as being optional, mineral wool or glass fiber insulation or polyethylene foam backer rod may be used as a permanent form to facilitate installation of the fill material. In floors constructed of hollow-core precast concrete units, packing material to be recessed from both top and bottom surfaces of floor, as required to accommodate fill material (Item 4B). When steel sleeve projects from top of floor or from both sides of wall, the thickness of mineral wool batt packing material should be increased by an amount equal to the distance that the sleeve extends past the floor or wall surface.

B. **Fill, Void or Cavity Material - Sealant** - Fill material applied within annulus, flush with top surface of floor assembly or top edge of steel sleeve. In walls and in floors constructed from hollow core precast concrete units, fill material applied symmetrically on both sides of assembly flush with wall/floor surfaces or both ends of steel sleeve. At point contact location, apply min 1/4 in. (6 mm) bead of fill material at pipe/concrete interface or pipe/steel sleeve interface on top surface of floor or both surfaces of wall or precast concrete units. The fill material thickness shall be as specified in the following table:

Min Concrete Thickness, in. (mm)	Steel Sleeve	Max Annular Space, in. (mm)	Packing Material	Min Fill Material Thickness, in. (mm)	F Rating
2-1/2 (64)	Optional	2 (51)	Required	1/4 (6)	3 hr
4-1/2 (114)	Optional	1 (25)	Optional	1/2 (13)	2 hr

**SPECIFIED TECHNOLOGIES INC - SpecSeal LCI Sealant**  
\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

1. **Floor or Wall Assembly** - Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m<sup>3</sup>) concrete. Wall may also be constructed of any UL Classified Concrete Blocks.

2. **Firestop Device** - The range-taking Grid System shall be installed in accordance with the accompanying installation instructions. The Grid System provides one to four slots for mounting banks of four "ganged" firestop device modules and is made up of multiple steel components. End, side and splice brackets shall be secured together forming various rectangular Grid Systems by means of bolts and nuts (provided) located at each corner. The Grid System may be installed blank through the use of unlaminated cover plates, steel clips and steel holders. The Grid System shall be activated with optional rows of "ganged" firestop device modules. Optional "ganged" modules with holder plates shall be placed into open slots within the Grid Systems and shall be secured to the steel frame through the use of bolts and nuts (provided). The frame of the Grid System shall be installed with gasketing material (provided) and secured to the top surface of the floor or one surface of the wall through predrilled openings located on the grid brackets using min 3/16 in. (4.8 mm) diam by 1-1/4 in. (32 mm) long steel concrete screws. As an alternate to the steel concrete screws, min 1-1/4 in. (32 mm) long steel powder actuated fasteners provided with min 3/4 in. (19 mm) diam steel washers may be used. As an option in walls, a second frame of the Grid System may be installed on the second side of the wall. Each firestop device module consists of a 4 by 4-5/8 by 14 in. (102 by 118 by 356 mm) long galv steel tube with an intumescent material lining. Series 44 device modules have spring loaded steel retainers plates. Firestop device modules to be installed in accordance with the accompanying installation instructions. Four device modules are "ganged" together by means of an integral hook and eye window attachments. Two holder plates, one on each side of the four "ganged" modules, are to be attached to each end module using an integral hook and eye window attachment. The space between the firestop device and the periphery of the opening shall be min 0 in. (point contact) to max 1-1/4 in. (32 mm). As an option, firestop devices may be cast or grouted into floor or wall assembly. The opening size and maximum number of pathway modules for each Grid System shall be as shown in the following table:

1. **Floor or Wall Assembly** - Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m<sup>3</sup>) concrete. Wall may also be constructed of any UL Classified Concrete Blocks.

2. **Firestop Device** - The range-taking Grid System shall be installed in accordance with the accompanying installation instructions. The Grid System provides one to four slots for mounting banks of four "ganged" firestop device modules and is made up of multiple steel components. End, side and splice brackets shall be secured together forming various rectangular Grid Systems by means of bolts and nuts (provided) located at each corner. The Grid System may be installed blank through the use of unlaminated cover plates, steel clips and steel holders. The Grid System shall be activated with optional rows of "ganged" firestop device modules. Optional "ganged" modules with holder plates shall be placed into open slots within the Grid Systems and shall be secured to the steel frame through the use of bolts and nuts (provided). The frame of the Grid System shall be installed with gasketing material (provided) and secured to the top surface of the floor or one surface of the wall through predrilled openings located on the grid brackets using min 3/16 in. (4.8 mm) diam by 1-1/4 in. (32 mm) long steel concrete screws. As an alternate to the steel concrete screws, min 1-1/4 in. (32 mm) long steel powder actuated fasteners provided with min 3/4 in. (19 mm) diam steel washers may be used. As an option in walls, a second frame of the Grid System may be installed on the second side of the wall. Each firestop device module consists of a 4 by 4-5/8 by 14 in. (102 by 118 by 356 mm) long galv steel tube with an intumescent material lining. Series 44 device modules have spring loaded steel retainers plates. Firestop device modules to be installed in accordance with the accompanying installation instructions. Four device modules are "ganged" together by means of an integral hook and eye window attachments. Two holder plates, one on each side of the four "ganged" modules, are to be attached to each end module using an integral hook and eye window attachment. The space between the firestop device and the periphery of the opening shall be min 0 in. (point contact) to max 1-1/4 in. (32 mm). As an option, firestop devices may be cast or grouted into floor or wall assembly. The opening size and maximum number of pathway modules for each Grid System shall be as shown in the following table:

3. **Cables** - Cables may represent a 0 to 100 percent visual fill within the loading area for the firestop device modules. Cables to be rigidly supported on both sides of the floor or wall assembly. Any combination of the following types of cables may be used:

A. Max 400 pair No. 24 AWG (or smaller) copper conductor telecommunication cable with polyvinyl chloride (PVC) or plenum-rated jacketing and insulation.  
B. Max 750 kcmil single copper conductor power cable with XLPE jacket and insulation or plenum-rated jacketing and insulation.  
C. Max 7/8 No. 12 AWG copper conductor control cable with PVC or XLPE jacket and insulation or plenum-rated jacketing and insulation.  
D. Max 3/8 No. 8 AWG NM cable (Romex) with PVC insulation and jacket or plenum-rated jacketing and insulation.  
E. Max 400 pair No. 22 AWG (or smaller) copper conductor data cable with PVC or plenum rated jacketing and insulation.  
F. Coaxial cable with fluorinated ethylene or PVC insulation and jacketing or plenum rated jacketing and insulation having a max diam of 5/8 in. (16 mm).  
G. Optical fiber cable with PVC or polyethylene (PE) jacket and insulation or plenum rated jacketing and insulation having a max diam of 5/8 in. (16 mm).

4. **Firestop Device** - Not Shown - Optional - Nom 2 in. (51 mm) thick blank to be installed in accordance with the accompanying installation instructions. Blanket tightly wrapped around grouped cables and pathway devices to extend 36 in. (914 mm) above floor or both sides of the wall and secured with integral closure straps.

5. **Duct Wrap Material** - Not Shown - Optional, for use in lieu of item 4 - Nom 2 in. (51 mm) thick duct wrap tightly wrapped around grouped cables and pathway devices to extend 36 in. (914 mm) above floor or both sides of the wall. All longitudinal seams of duct wrap to be sealed with fire tape.

**THERMAL CERAMICS INC - FireMaster FastWrap XL or Pyscoat Duct Wrap XL**

**NOTE: When Item 4 or 5 is used the T, FT and FTH Ratings are 2 hr. Otherwise, the T, FT and FTH Ratings are 0 hr.**  
\*Bearing the UL Listing Mark.  
\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

**Specified Technologies Inc. 210 Evans Way Somerville, NJ 08876**  
Reproduced courtesy of Underwriters Laboratories, Inc.  
Created or Revised: October 10, 2018  
(800)992-1180 • (908)526-8000 • FAX (908)231-8415 • E-Mail: techserv@stfirestop.com • Website: www.stfirestop.com

Classified by Underwriters Laboratories, Inc. to ANSIUL 1479 (ASTM E814) and CANULC S115 System No. C-AJ-3317

ANSI/UL1479 (ASTM E814)	CANULC S115
F Rating - 3 Hr	F Rating - 3 Hr
T Ratings - 0 and 2 Hr (See Items 4 and 5)	FT Ratings - 0 and 2 Hr (See Items 4 and 5)
	FH Rating - 3 Hr
	FTH Ratings - 0 and 2 Hr (See Items 4 and 5)

1. **Floor or Wall Assembly** - Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m<sup>3</sup>) concrete. Wall may also be constructed of any UL Classified Concrete Blocks.

2. **Firestop Device** - The range-taking Grid System shall be installed in accordance with the accompanying installation instructions. The Grid System provides one to four slots for mounting banks of four "ganged" firestop device modules and is made up of multiple steel components. End, side and splice brackets shall be secured together forming various rectangular Grid Systems by means of bolts and nuts (provided) located at each corner. The Grid System may be installed blank through the use of unlaminated cover plates, steel clips and steel holders. The Grid System shall be activated with optional rows of "ganged" firestop device modules. Optional "ganged" modules with holder plates shall be placed into open slots within the Grid Systems and shall be secured to the steel frame through the use of bolts and nuts (provided). The frame of the Grid System shall be installed with gasketing material (provided) and secured to the top surface of the floor or one surface of the wall through predrilled openings located on the grid brackets using min 3/16 in. (4.8 mm) diam by 1-1/4 in. (32 mm) long steel concrete screws. As an alternate to the steel concrete screws, min 1-1/4 in. (32 mm) long steel powder actuated fasteners provided with min 3/4 in. (19 mm) diam steel washers may be used. As an option in walls, a second frame of the Grid System may be installed on the second side of the wall. Each firestop device module consists of a 4 by 4-5/8 by 14 in. (102 by 118 by 356 mm) long galv steel tube with an intumescent material lining. Series 44 device modules have spring loaded steel retainers plates. Firestop device modules to be installed in accordance with the accompanying installation instructions. Four device modules are "ganged" together by means of an integral hook and eye window attachments. Two holder plates, one on each side of the four "ganged" modules, are to be attached to each end module using an integral hook and eye window attachment. The space between the firestop device and the periphery of the opening shall be min 0 in. (point contact) to max 1-1/4 in. (32 mm). As an option, firestop devices may be cast or grouted into floor or wall assembly. The opening size and maximum number of pathway modules for each Grid System shall be as shown in the following table:

1. **Floor or Wall Assembly** - Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m<sup>3</sup>) concrete. Wall may also be constructed of any UL Classified Concrete Blocks.

2. **Firestop Device** - The range-taking Grid System shall be installed in accordance with the accompanying installation instructions. The Grid System provides one to four slots for mounting banks of four "ganged" firestop device modules and is made up of multiple steel components. End, side and splice brackets shall be secured together forming various rectangular Grid Systems by means of bolts and nuts (provided) located at each corner. The Grid System may be installed blank through the use of unlaminated cover plates, steel clips and steel holders. The Grid System shall be activated with optional rows of "ganged" firestop device modules. Optional "ganged" modules with holder plates shall be placed into open slots within the Grid Systems and shall be secured to the steel frame through the use of bolts and nuts (provided). The frame of the Grid System shall be installed with gasketing material (provided) and secured to the top surface of the floor or one surface of the wall through predrilled openings located on the grid brackets using min 3/16 in. (4.8 mm) diam by 1-1/4 in. (32 mm) long steel concrete screws. As an alternate to the steel concrete screws, min 1-1/4 in. (32 mm) long steel powder actuated fasteners provided with min 3/4 in. (19 mm) diam steel washers may be used. As an option in walls, a second frame of the Grid System may be installed on the second side of the wall. Each firestop device module consists of a 4 by 4-5/8 by 14 in. (102 by 118 by 356 mm) long galv steel tube with an intumescent material lining. Series 44 device modules have spring loaded steel retainers plates. Firestop device modules to be installed in accordance with the accompanying installation instructions. Four device modules are "ganged" together by means of an integral hook and eye window attachments. Two holder plates, one on each side of the four "ganged" modules, are to be attached to each end module using an integral hook and eye window attachment. The space between the firestop device and the periphery of the opening shall be min 0 in. (point contact) to max 1-1/4 in. (32 mm). As an option, firestop devices may be cast or grouted into floor or wall assembly. The opening size and maximum number of pathway modules for each Grid System shall be as shown in the following table:

3. **Cables** - Cables may represent a 0 to 100 percent visual fill within the loading area for the firestop device modules. Cables to be rigidly supported on both sides of the floor or wall assembly. Any combination of the following types of cables may be used:

A. Max 400 pair No. 24 AWG (or smaller) copper conductor telecommunication cable with polyvinyl chloride (PVC) or plenum-rated jacketing and insulation.  
B. Max 750 kcmil single copper conductor power cable with XLPE jacket and insulation or plenum-rated jacketing and insulation.  
C. Max 7/8 No. 12 AWG copper conductor control cable with PVC or XLPE jacket and insulation or plenum-rated jacketing and insulation.  
D. Max 3/8 No. 8 AWG NM cable (Romex) with PVC insulation and jacket or plenum-rated jacketing and insulation.  
E. Max 400 pair No. 22 AWG (or smaller) copper conductor data cable with PVC or plenum rated jacketing and insulation.  
F. Coaxial cable with fluorinated ethylene or PVC insulation and jacketing or plenum rated jacketing and insulation having a max diam of 5/8 in. (16 mm).  
G. Optical fiber cable with PVC or polyethylene (PE) jacket and insulation or plenum rated jacketing and insulation having a max diam of 5/8 in. (16 mm).

4. **Firestop Device** - Not Shown - Optional - Nom 2 in. (51 mm) thick blank to be installed in accordance with the accompanying installation instructions. Blanket tightly wrapped around grouped cables and pathway devices to extend 36 in. (914 mm) above floor or both sides of the wall and secured with integral closure straps.

5. **Duct Wrap Material** - Not Shown - Optional, for use in lieu of item 4 - Nom 2 in. (51 mm) thick duct wrap tightly wrapped around grouped cables and pathway devices to extend 36 in. (914 mm) above floor or both sides of the wall. All longitudinal seams of duct wrap to be sealed with fire tape.

**THERMAL CERAMICS INC - FireMaster FastWrap XL or Pyscoat Duct Wrap XL**

**NOTE: When Item 4 or 5 is used the T, FT and FTH Ratings are 2 hr. Otherwise, the T, FT and FTH Ratings are 0 hr.**  
\*Bearing the UL Listing Mark.  
\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

**Specified Technologies Inc. 210 Evans Way Somerville, NJ 08876**  
Reproduced courtesy of Underwriters Laboratories, Inc.  
Created or Revised: January 23, 2014  
(800)992-1180 • (908)526-8000 • FAX (908)231-8415 • E-Mail: techserv@stfirestop.com • Website: www.stfirestop.com

Classified by Underwriters Laboratories, Inc. to ANSIUL 1479 (ASTM E814) and CANULC S115 System No. C-AJ-3317

ANSI/UL1479 (ASTM E814)	CANULC S115
F Rating - 3 Hr	F Rating - 3 Hr
T Ratings - 0 and 2 Hr (See Items 4 and 5)	FT Ratings - 0 and 2 Hr (See Items 4 and 5)
	FH Rating - 3 Hr
	FTH Ratings - 0 and 2 Hr (See Items 4 and 5)

3A. **Through Penetrant Product - Flexible Metal Piping** - As an alternate to Item 3, one nom 2 in. (51 mm) diam (or smaller) flexible steel pipe (with or without plastic jacketing) to be installed either concentrically or eccentrically within the firestop system. The annular space between the pipe, conduit or tube and the periphery of the opening shall be min 0 in. (0 mm or point contact). The max annular space is 1 or 2 in. (25 or 51 mm) as shown in the table in item 4B. Pipe to be rigidly supported on both sides of the floor or wall assembly.

**OMEGA FLEX INC**  
**GASITTE, DIV OF TITFLEX**  
**WARD MFG L L C**

4. **Firestop System** - The firestop system shall consist of the following:

A. **Packing Material** - When required as shown in the table in Item 4B, min 4 pcf (64 kg/m<sup>3</sup>) mineral wool batt insulation, compressed and tightly packed to min 2-1/4 in. (57 mm) thickness. Packing material recessed from top surface of floor or both surfaces of wall as required to accommodate fill material (Item 4B). When packing material is shown as being optional, mineral wool or glass fiber insulation or polyethylene foam backer rod may be used as a permanent form to facilitate installation of the fill material. In floors constructed of hollow-core precast concrete units, packing material to be recessed from both top and bottom surfaces of floor, as required to accommodate fill material (Item 4B). When steel sleeve projects from top of floor or from both sides of wall, the thickness of mineral wool batt packing material should be increased by an amount equal to the distance that the sleeve extends past the floor or wall surface.

B. **Fill, Void or Cavity Material - Sealant** - Fill material applied within annulus, flush with top surface of floor assembly or top edge of steel sleeve. In walls and in floors constructed from hollow core precast concrete units, fill material applied symmetrically on both sides of assembly flush with wall/floor surfaces or both ends of steel sleeve. At point contact location, apply min 1/4 in. (6 mm) bead of fill material at pipe/concrete interface or pipe/steel sleeve interface on top surface of floor or both surfaces of wall or precast concrete units. The fill material thickness shall be as specified in the following table:

Min Concrete Thickness, in. (mm)	Steel Sleeve	Max Annular Space, in. (mm)	Packing Material	Min Fill Material Thickness, in. (mm)	F Rating
2-1/2 (64)	Optional	2 (51)	Required	1/4 (6)	3 hr
4-1/2 (114)	Optional	1 (25)	Optional	1/2 (13)	2 hr

**SPECIFIED TECHNOLOGIES INC - SpecSeal LCI Sealant**  
\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

1. **Floor or Wall Assembly** - Lightweight or normal weight (100-150 pcf or 1600-2400 kg/m<sup>3</sup>) concrete floor or wall. Min thickness of concrete is shown in table in Item 4B. Floor may also be constructed of any UL Classified Concrete Blocks. Max diam of opening is 14 in. (356 mm). Max diam of opening in floors constructed of hollow-core is 7 in. (178 mm).

2. **Steel Sleeve** - (Optional) - Nom 14 in. (356 mm) diam (or heavier) Schedule 10 (or heavier) steel pipe or No. 26 ga (0.022 in. or 0.56 mm) thick sheet steel sleeve with square anner flange spot welded to the sleeve at approx mid-height. Sleeve cast or grouted in place flush with floor or wall surfaces. Steel pipe sleeve may project a max of 2 in. (51 mm) beyond the floor or wall surfaces.

3. **Through Penetrant** - One metallic pipe, conduit or tube to be installed concentrically or eccentrically within the firestop system. The annular space between the pipe, conduit or tube and the periphery of the opening shall be min 0 in. (point contact). The max annular space is 1 in. or 2 in. (25 or 51 mm) as shown in the table in item 4B. Pipe, conduit or tube to be rigidly supported on both sides of the floor or wall assembly. The following types and sizes of metallic pipes, conduits and tubes may be used:

A. **Steel Pipe** - Nom 12 in. (305 mm) diam (or smaller) Schedule 5 (or heavier) steel pipe.  
B. **Iron Pipe** - Nom 12 in. (305 mm) diam (or smaller) cast or ductile iron pipe.  
C. **Conduit** - Nom 6 in. (152 mm) diam (or smaller) rigid steel conduit, nom 4 in. (102 mm) diam (or smaller) steel electrical metallic tubing (EMT) or nom 4 in. (102 mm) diam (or smaller) flexible steel conduit.  
D. **Copper Pipe** - Nom 4 in. (102 mm) diam (or smaller) Regular (or heavier) copper pipe.  
E. **Copper Tube** - Nom 4 in. (102 mm) diam (or smaller) Regular L (or heavier) copper tube.

**Specified Technologies Inc. 210 Evans Way Somerville, NJ 08876**  
Reproduced courtesy of Underwriters Laboratories, Inc.  
Created or Revised: January 23, 2014  
(800)992-1180 • (908)526-8000 • FAX (908)231-8415 • E-Mail: techserv@stfirestop.com • Website: www.stfirestop.com

Classified by Underwriters Laboratories, Inc. to ANSIUL 1479 (ASTM E814) and CANULC S115 System No. C-AJ-3317

ANSI/UL1479 (ASTM E814)	CANULC S115
F Rating - 3 Hr	F Rating - 3 Hr
T Rating - 0 Hr	FT Rating - 0 Hr
L Rating At Ambient - Less Than 1 CFM/sq ft	FH Rating - 3 Hr
L Rating At 400 F - Less Than 1 CFM/sq ft	FTH Rating - 0 Hr
	L Rating At Ambient - Less Than 1 CFM/sq ft
	L Rating At 400 F - Less Than 1 CFM/sq ft

1. **Floor or Wall Assembly** - Lightweight or normal weight (100-150 pcf or 1600-2400 kg/m<sup>3</sup>) concrete floor or wall. Min thickness of concrete is shown in table in Item 4B. Floor may also be constructed of any UL Classified Concrete Blocks. Max diam of opening is 14 in. (356 mm). Max diam of opening in floors constructed of hollow-core is 7 in. (178 mm).

2. **Steel Sleeve** - (Optional) - Nom 14 in. (356 mm) diam (or heavier) Schedule 10 (or heavier) steel pipe or No. 26 ga (0.022 in. or 0.56 mm) thick sheet steel sleeve with square anner flange spot welded to the sleeve at approx mid-height. Sleeve cast or grouted in place flush with floor or wall surfaces. Steel pipe sleeve may project a max of 2 in. (51 mm) beyond the floor or wall surfaces.

3. **Through Penetrant** - One metallic pipe, conduit or tube to be installed concentrically or eccentrically within the firestop system. The annular space between the pipe, conduit or tube and the periphery of the opening shall be min 0 in. (point contact). The max annular space is 1 in. or 2 in. (25 or 51 mm) as shown in the table in item 4B. Pipe, conduit or tube to be rigidly supported on both sides of the floor or wall assembly. The following types and sizes of metallic pipes, conduits and tubes may be used:

A. **Steel Pipe** - Nom 12 in. (305 mm) diam (or smaller) Schedule 5 (or heavier) steel pipe.  
B. **Iron Pipe** - Nom 12 in. (305 mm) diam (or smaller) cast or ductile iron pipe.  
C. **Conduit** - Nom 6 in. (152 mm) diam (or smaller) rigid steel conduit, nom 4 in. (102 mm) diam (or smaller) steel electrical metallic tubing (EMT) or nom 4 in. (102 mm) diam (or smaller) flexible steel conduit.  
D. **Copper Pipe** - Nom 4 in. (102 mm) diam (or smaller) Regular (or heavier) copper pipe.  
E. **Copper Tube** - Nom 4 in. (102 mm) diam (or smaller) Regular L (or heavier) copper tube.

**Specified Technologies Inc. 210 Evans Way Somerville, NJ 08876**  
Reproduced courtesy of Underwriters Laboratories, Inc.  
Created or Revised: January 23, 2014  
(800)992-1180 • (908)526-8000 • FAX (908)231-8415 • E-Mail: techserv@stfirestop.com • Website: www.stfirestop.com

Classified by Underwriters Laboratories, Inc. to ANSIUL 1479 (ASTM E814) and CANULC S115 System No. C-AJ-3317

ANSI/UL1479 (ASTM E814)	CANULC S115
F Rating - 3 Hr	F Rating - 3 Hr
T Rating - 1 Hr	FT Rating - 1 Hr

1. **Floor or Wall Assembly** - Min 4-1/2 in. thick lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified Concrete Blocks.

2. **Steel Sleeve** - Nom 2 in. (51 mm) diam (or smaller) Schedule 10 (or heavier) steel pipe or rigid steel conduit sleeve cast or grouted into concrete floor or wall. End of sleeve to project 2 in. beyond top surface of floor or beyond both surfaces of wall.

3. **Cables** - Cables to be max 4 pair No. 24 AWG (or smaller) copper conductor cables with polyvinyl chloride (PVC) insulation and jacket or max 4 pair No. 24 AWG (or smaller) copper conductor cables intended for plenum applications. Aggregate cross-sectional area of cables to be max 40 percent of the aggregate cross-sectional area of the steel sleeve (Item 2). The annular space within the firestop system shall be a min of 1/4 in. to a max of 1 in. Cables to be rigidly supported on both sides of floor or wall assembly.

4. **Packing Material** - (Optional) - Open or closed cell polyethylene or polyurethane foam backer rod used as a form to prevent leakage of the fill material. Packing material to be recessed from end of sleeve as required to accommodate the required thickness of fill material.

5. **Fill, Void or Cavity Material - Putty or Sealant** - Min 1 in. thickness applied within annulus flush with top edge of sleeve in floors or both edges of sleeve in walls.

**SPECIFIED TECHNOLOGIES INC - SpecSeal 100, 101, 102, 105, 120 or 129 Sealant, SpecSeal Putty**  
\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

**Specified Technologies Inc. 210 Evans Way Somerville, NJ 08876**  
Reproduced courtesy of Underwriters Laboratories, Inc.  
Created or Revised: January 23, 2014  
(800)992-1180 • (908)526-8000 • FAX (908)231-8415 • E-Mail: techserv@stfirestop.com • Website: www.stfirestop.com

Classified by Underwriters Laboratories, Inc. to ANSIUL 1479 (ASTM E814) and CANULC S115 System No. C-AJ-3317

ANSI/UL1479 (ASTM E814)	CANULC S115
F Rating - 3 Hr	F Rating - 3 Hr
T Rating - 1 Hr	FT Rating - 1 Hr

1. **Floor or Wall Assembly** - Min 4-1/2 in. thick lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified Concrete Blocks.

2. **Steel Sleeve** - Nom 2 in. (51 mm) diam (or smaller) Schedule 10 (or heavier) steel pipe or rigid steel conduit sleeve cast or grouted into concrete floor or wall. End of sleeve to project 2 in. beyond top surface of floor or beyond both surfaces of wall.

3. **Cables** - Cables to be max 4 pair No. 24 AWG (or smaller) copper conductor cables with polyvinyl chloride (PVC) insulation and jacket or max 4 pair No. 24 AWG (or smaller) copper conductor cables intended for plenum applications. Aggregate cross-sectional area of cables to be max 40 percent of the aggregate cross-sectional area of the steel sleeve (Item 2). The annular space within the firestop system shall be a min of 1/4 in. to a max of 1 in. Cables to be rigidly supported on both sides of floor or wall assembly.

4. **Packing Material** - (Optional) - Open or closed cell polyethylene or polyurethane foam backer rod used as a form to prevent leakage of the fill material. Packing material to be recessed from end of sleeve as required to accommodate the required thickness of fill material.

5. **Fill, Void or Cavity Material - Putty or Sealant** - Min 1 in. thickness applied within annulus flush with top edge of sleeve in floors or both edges of sleeve in walls.

**SPECIFIED TECHNOLOGIES INC - SpecSeal 100, 101, 102, 105, 120 or 129 Sealant, SpecSeal Putty**  
\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

**Specified Technologies Inc. 210 Evans Way Somerville, NJ 08876**  
Reproduced courtesy of Underwriters Laboratories, Inc.  
Created or Revised: January 23, 2014  
(800)992-1180 • (908)526-8000 • FAX (908)231-8415 • E-Mail: techserv@stfirestop.com • Website: www.stfirestop.com

Classified by Underwriters Laboratories, Inc. to ANSIUL 1479 (ASTM E814) and CANULC S115 System No. C-AJ-3317

ANSI/UL1479 (ASTM E814)	CANULC S115
F Rating - 3 Hr	F Rating - 3 Hr
T Rating - 1 Hr	FT Rating - 1 Hr

1. **Floor or Wall Assembly** - Min 4-1/2 in. thick lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified Concrete Blocks.

2. **Steel Sleeve** - Nom 2 in. (51 mm) diam (or smaller) Schedule 10 (or heavier) steel pipe or rigid steel conduit sleeve cast or grouted into concrete floor or wall. End of sleeve to project 2 in. beyond top surface of floor or beyond both surfaces of wall.

3. **Cables** - Cables to be max 4 pair No. 24 AWG (or smaller) copper conductor cables with polyvinyl chloride (PVC) insulation and jacket or max 4 pair No. 24 AWG (or smaller) copper conductor cables intended for plenum applications. Aggregate cross-sectional area of cables to be max 40 percent of the aggregate cross-sectional area of the steel sleeve (Item 2). The annular space within the firestop system shall be a min of 1/4 in. to a max of 1 in. Cables to be rigidly supported on both sides of floor or wall assembly.

4. **Packing Material** - (Optional) - Open or closed cell polyethylene or polyurethane foam backer rod used as a form to prevent leakage of the fill material. Packing material to be recessed from end of sleeve as required to accommodate the required thickness of fill material.

5. **Fill, Void or Cavity Material - Putty or Sealant** - Min 1 in. thickness applied within annulus flush with top edge of sleeve in floors or both edges of sleeve in walls.

**SPECIFIED TECHNOLOGIES INC - SpecSeal 100, 101, 102, 105, 120 or 129 Sealant, SpecSeal Putty**  
\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

**Specified Technologies Inc. 210 Evans Way Somerville, NJ 08876**  
Reproduced courtesy of Underwriters Laboratories, Inc.  
Created or Revised: October 30, 2018  
(800)992-1180 • (908)526-8000 • FAX (908)231-8415 • E-Mail: techserv@stfirestop.com • Website: www.stfirestop.com

Classified by Underwriters Laboratories, Inc. to ANSIUL 1479 (ASTM E814) and CANULC S115 System No. C-AJ-3317

ANSI/UL1479 (ASTM E814)	CANULC S115
F Rating - 3 Hr	F Rating - 3 Hr
T Rating - 1 Hr	FT Rating - 1 Hr

1. **Floor or Wall Assembly** - Min 4-1/2 in. thick lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified Concrete Blocks.

2. **Steel Sleeve** - Nom 2 in. (51 mm) diam (or smaller) Schedule 10 (or heavier) steel pipe or rigid steel conduit sleeve cast or grouted into concrete floor or wall. End of sleeve to project 2 in. beyond top surface of floor or beyond both surfaces of wall.

3. **Cables** - Cables to be max 4 pair No. 24 AWG (or smaller) copper conductor cables with polyvinyl chloride (PVC) insulation and jacket or max 4 pair No. 24 AWG (or smaller) copper conductor cables intended for plenum applications. Aggregate cross-sectional area of cables to be max 40 percent of the aggregate cross-sectional area of the steel sleeve (Item 2). The annular space within the firestop system shall be a min of 1/4 in. to a max of 1 in. Cables to be rigidly supported on both sides of floor or wall assembly.

4. **Packing Material** - (Optional) - Open or closed cell polyethylene or polyurethane foam backer rod used as a form to prevent leakage of the fill material. Packing material to be recessed from end of sleeve as required to accommodate the required thickness of fill material.

5. **Fill, Void or Cavity Material - Putty or Sealant** - Min 1 in. thickness applied within annulus flush with top edge of sleeve in floors or both edges of sleeve in walls.

**SPECIFIED TECHNOLOGIES INC - SpecSeal 100, 101, 102, 105, 120 or 129 Sealant, SpecSeal Putty**  
\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

**Specified Technologies Inc. 210 Evans Way Somerville, NJ 08876**  
Reproduced courtesy of Underwriters Laboratories, Inc.  
Created or Revised: October 30,







COMcheck Software Version 4.1.5.5 Interior Lighting Compliance Certificate

Project Information: Energy Code: 2015 IECC, Project Title: Swift Creek Elementary School, Project Type: New Construction

Construction Site: 5601 Tryon Rd, Raleigh, NC 27606, Designer/Contractor: CMTA, 10411 Meeting St, Louisville, KY 40059

Table for Allowed Interior Lighting Power with columns: Area Category, Floor Area (ft2), Allowed Watts / ft2, Allowed Watts (B X C)

Table for Proposed Interior Lighting Power with columns: Fixture ID, Description, Lamp/Wattage/Ballast, Lamps/Fixture, # of Fixtures, Watt, (C X D)

Project Title: Swift Creek Elementary School, Report date: 12/21/23, Data filename: V:\Projects\VSCS21 Swift Creek ES2, Design\11, ComCheck\SWIFT CREEK ELEMENTARY SCHOC Page 1 of 8

Table for Proposed Interior Lighting Power (continued) with columns: Fixture ID, Description, Lamp/Wattage/Ballast, Lamps/Fixture, # of Fixtures, Watt, (C X D)

Interior Lighting PASSES: Design 44% better than code, Compliance Statement, Kishan Patel - Electrical Engineer, Date: 02/02/2024

Project Title: Swift Creek Elementary School, Report date: 12/21/23, Data filename: V:\Projects\VSCS21 Swift Creek ES2, Design\11, ComCheck\SWIFT CREEK ELEMENTARY SCHOC Page 2 of 8

COMcheck Software Version 4.1.5.5 Exterior Lighting Compliance Certificate

Project Information: Energy Code: 2015 IECC, Project Title: Swift Creek Elementary School, Project Type: New Construction, Exterior Lighting Zone: 2 (Residential mixed use area (LZZ))

Construction Site: 5601 Tryon Rd, Raleigh, NC 27606, Designer/Contractor: CMTA, 10411 Meeting St, Louisville, KY 40059

Table for Allowed Exterior Lighting Power with columns: Area/Surface Category, Quantity, Allowed Watts / Unit, Traddable Wattage, Allowed Watts (B X C)

(a) Wattage tradeoffs are only allowed between tradable areas/surfaces. (b) A supplemental allowance equal to 600 watts may be applied toward compliance of both non-tradable and tradable areas/surfaces.

Table for Proposed Exterior Lighting Power with columns: Fixture ID, Description, Lamp/Wattage/Ballast, Lamps/Fixture, # of Fixtures, Watt, (C X D)

Exterior Lighting PASSES: Design 59% better than code, Exterior Lighting Compliance Statement, Kishan Patel - Electrical Engineer, Date: 02/02/2024

Project Title: Swift Creek Elementary School, Report date: 12/21/23, Data filename: V:\Projects\VSCS21 Swift Creek ES2, Design\11, ComCheck\SWIFT CREEK ELEMENTARY SCHOC Page 3 of 8

2018 APPENDIX B BUILDING CODE SUMMARY FOR ALL COMMERCIAL PROJECTS ELECTRICAL DESIGN (PROVIDE ON THE ELECTRICAL SHEETS IF APPLICABLE)

ELECTRICAL SUMMARY

Method of Compliance: Energy Code: ASHRAE 90.1: Prescriptive Performance

Lighting schedule (each fixture type): lamp type required in fixture, number of lamps in fixture, ballast type used in the fixture, number of ballasts in fixture, total wattage per fixture, total interior wattage specified vs. allowed (whole building or space by space), total exterior wattage specified vs. allowed

- Additional Efficiency Package Options: (When using the 2018 NCEC; not required for ASHRAE 90.1) C406.2 More Efficient Mechanical Equipment, C406.3 Reduced Lighting Power Density, C406.4 Enhanced Digital Lighting Controls, C406.5 On-Site Renewable Energy, C406.6 Dedicated Outdoor Air System, C406.7 Reduced Energy Use in Service Water Heating

2018 NC Administrative Code and Policies Appendix B for Building



Wake County Public School System



434 FAYETTEVILLE STREET SUITE 1700 RALEIGH, NORTH CAROLINA 27601



04/10/2024

Swift Creek Elementary School, 5601 Tryon Rd, Raleigh, NC 27606, LSP PROJECT: 9201-207411

Table with columns: DATE, DESCRIPTION

SHEET NAME: COMCHECK - ELEMENTARY SCHOOL

BID SET SUBMISSION: 2024.04.10

SHEET: E00.05

BID SET



THE LINE SHOWN ABOVE IS EXACTLY ONE FOOT FROM THE EXISTING CURB LINE.

E

D

C

B

A

1

# ELECTRICAL SITE UTILITY PLAN

NO SCALE

1

2

3

4

5

6

## UTILITY LEGEND



- PRI --- UNDERGROUND ELECTRICAL UTILITY PRIMARY
- SEC --- UNDERGROUND ELECTRICAL SERVICE SECONDARY
- UGE --- UNDERGROUND ELECTRIC
- UGT --- UNDERGROUND TELECOMMUNICATIONS
- B --- UNDERGROUND BRANCH CIRCUIT
- HH HANDHOLE

## GENERAL NOTES (SITE):

- A. DO NOT SCALE FROM MECHANICAL AND ELECTRICAL DRAWINGS. FIELD VERIFY REQUIRED DIMENSIONS AND COORDINATE WITH CIVIL DRAWINGS AND SURVEYS.
- B. REFER ALSO TO ALL OTHER PLANS AND THE SPECIFICATION, BUT ESPECIALLY TO: THE SITE SURVEY, THE ARCHITECTURAL SITE PLAN, THE SITE GRADING PLAN, THE PLANTING PLAN (WHERE AVAILABLE), FOUNDATION PLANS, APPROPRIATE MECHANICAL & ELECTRICAL FLOOR PLANS FOR SERVICE CONTINUATIONS, THE SITE UTILITY PLAN - MECHANICAL & ELECTRICAL. WHERE THERE ARE CONFLICTS AMONG THESE PLANS AND/OR RELATED SPECIFICATIONS, ADVISE THESE ENGINEERS AT LEAST TEN DAYS PRIOR TO SUBMISSION OF BIDS.
- C. ALL FEES AND ANY OTHER COSTS TO UTILITY COMPANIES, MUNICIPALITIES, INSPECTORS, REVIEWING AGENCIES, ETC. ARE TO BE INCLUDED AS A PART OF THIS CONTRACT.
- D. FEDERAL, STATE, LOCAL, MUNICIPALITY AND UTILITY COMPANY CODES, RULES, REGULATIONS AND REQUIREMENTS APPLY UNLESS EXCEEDED BY THIS DESIGN.
- E. WHEN INTERRUPTION OF AN EXISTING UTILITY OR SERVICE IS PLANNED OR OCCURS ACCIDENTALLY, THE CONTRACTOR(S) SHALL WORK CONTINUOUSLY AS NEEDED TO RESTORE SAME PROVIDING PREMIUM TIME AS NEEDED AT NO INCREASE IN THE CONTRACT PRICE.
- F. LOCATIONS, DEPTHS, MATERIAL TYPES, ELEVATIONS, ETC. OF ALL APPURTENANCES, LINES, BUILDINGS, ETC. INDICATED ON THESE DRAWINGS WERE TAKEN FROM VARIOUS SOURCES. ARE DIAGRAMMATIC ONLY AND ARE SUBJECT TO SUBSTANTIAL VARIATION FROM EXISTING CONDITIONS. EXISTING UTILITIES LOCATIONS MAY VARY. CONSEQUENTLY ALL CONTRACTORS SHALL EXERCISE EXTREME CARE IN THE COURSE OF THEIR WORK SO AS TO ENSURE THAT THEY DO NOT INTERRUPT ANY EXISTING SERVICE. FOR SAFETY PURPOSES, PAY PARTICULAR ATTENTION TO THIS PRECAUTION RELATIVE TO NATURAL GAS AND ELECTRICAL LINES. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL FEDERAL, STATE, AND/OR LOCAL RULES, REGULATIONS, STANDARDS AND SAFETY REQUIREMENTS.
- G. PROVIDE LONG RADIUS ELBOWS FOR UNDERGROUND CONDUIT BENDS. WHERE SERVING A UTILITY OWNED TRANSFORMER, THE UTILITY STANDARDS SHALL TAKE PRECEDENCE.
- H. UTILITIES SHALL BE INSTALLED IN ACCORDANCE WITH THE APPLICABLE MUNICIPALITY OR UTILITY COMPANY STANDARDS. IN ALL CASES, THE MOST STRINGENT REQUIREMENT SHALL APPLY. IF ANY VARIATION OCCURS, CONSULT THE ENGINEER. CONTRACTOR SHALL VISIT THE SITE AND FIELD VERIFY THE ROUTING OF ALL UTILITIES NEW AND EXISTING PRIOR TO SUBMISSION OF BIDS. SUBMISSION OF A BID PROPOSAL INDICATES THAT THE CONTRACTOR IS FULLY AWARE OF ALL OBSTRUCTIONS AND WILL INSTALL ALL OF THE NEW UTILITIES WITHOUT REQUESTS FOR ANY ADDITIONAL CHANGES.
- I. PROVIDE GALVANIZED RIGID CONDUIT FOR EXTERIOR UNDERGROUND TRANSITIONS TO ABOVE GRADE. EXTEND CONDUIT A MINIMUM OF 6" ABOVE GRADE.
- J. CONTRACTOR SHALL CONTACT ENGINEER FOR INSPECTION OF TRENCHES PRIOR TO INSTALLATION OF CONDUITS OR RACEWAYS. PROVIDE PHOTOS UPON REQUEST.
- K. CONTRACTOR SHALL CUT AND PATCH ALL PAVEMENT, CURBING, ETC. AS REQUIRED FOR WORK. CONTRACTOR SHALL REPAIR ALL LANDSCAPING THAT IS DAMAGED FOR WORK. FINISH GRADE, SEED AND STRAW ALL DISTURBED GREEN SPACES. ALL PATCH AND REPAIR WORK SHALL BE IN ACCORDANCE WITH BOTH CIVIL AND LANDSCAPE DRAWINGS AND SPECIFICATIONS.

## KEYNOTES

- U7 PROVIDE PATHWAYS AND CABLING FOR LIFT STATION. COORDINATE EXACT LOCATIONS FOR FINAL CONNECTIONS WITH LIFT STATION CONTRACTOR. REFER TO FEEDER SCHEDULE FOR CONDUCTOR SIZES.
- U8 PROVIDE TWO (2) 2" UNDERGROUND CONDUIT, STUBBED UP IN ELECTRICAL ROOM INDICATED. TO IN-GRADE 24"x36" HAND-HOLE FOR FUTURE POWER CONNECTIONS. REFER TO TYPICAL ELECTRICAL HAND-HOLE DETAIL.
- U9 PROVIDE TWO (2) 2" UNDERGROUND CONDUIT, STUBBED UP IN IDF/MDF ROOM INDICATED. TO IN-GRADE 24"x36" HAND-HOLE FOR FUTURE TELECOM CONNECTIONS. REFER TO TYPICAL TELECOM HAND-HOLE DETAIL.
- U10 GENERAL PARKING LOT LIGHTING AND POLES ARE UTILITY PROVIDED AND OWNED VIA LEASE AGREEMENT. COORDINATE WITH UTILITY FOR DIRECTIONAL BORING UNDER DRIVEWAYS.
- U11 PROVIDE TAMPER SWITCHES AND MONITORING FOR BACKFLOW PREVENTER VALVES. TIE INTO FIRE ALARM LOOP. COORDINATE EXACT LOCATIONS WITH CIVIL DRAWINGS.
- U12 PROVIDE 20A/1P, MOTOR RATED SWITCH FOR BACKFLOW PREVENTER ENCLOSURE HEATER. SEE CIVIL DRAWINGS FOR MORE INFORMATION.



Wake County Public School System



434 FAYETTEVILLE STREET SUITE 1700  
RALEIGH, NORTH CAROLINA 27601  
TEL. 919.829.2730 FAX. 919.829.2700  
WWW.LS3P.COM



04/10/2024  
COPYRIGHT 2024 ALL RIGHTS RESERVED. PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

Swift Creek Elementary School

5601 Tryon Rd Raleigh, NC 27606

LS3P PROJECT: 9201-207411

DATE	DESCRIPTION

SHEET NAME:  
ELECTRICAL SITE UTILITY PLAN

BID SET SUBMISSION: 2024.04.10

SHEET:  
**E01.00**

BID SET

4/9/2024 3:58:49 PM
































































































































































































































4/2/2024 4:06:56 PM



Wake County Public School System



434 FAYETTEVILLE STREET SUITE 1700  
 RALEIGH, NORTH CAROLINA 27601  
 TEL. 919.829.2730 FAX. 919.829.2700  
 WWW.LS3P.COM



04/10/2024  
 COPYRIGHT 2024 ALL RIGHTS RESERVED. PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

**Swift Creek Elementary School**  
 5601 Tryon Rd Raleigh, NC 27606  
 LSP PROJECT: 9201-207411

DATE	DESCRIPTION

**SHEET NAME:**  
 ELECTRICAL DETAILS

**BID SET SUBMISSION:** 2024.04.10

**SHEET:**  
**E09.06**

BID SET























4/2/2024 4:07:16 PM  
E  
D  
C  
B  
A

DISTRIBUTION PANELBOARD AND WIRING SCHEDULE										
SWITCHBOARD: LDP1B			MAINS TYPE: MCB			SCCR (KA): 10				
VOLTAGE: 208Y/120V/3P/4W			SPD: No			AVAIL FAULT CURRENT (KA): 5.8				
AMPERES: 400 A			MOUNTING: SURFACE			SUPPLY FROM: T-LDP1B				
CKT	CIRCUIT DESCRIPTION	SETS	WIRE	GND	COND	POLES	FRAME	TRIP	Load	REMARKS
1	LR1B	1	(4) #30	#3	2"	3	200 A	150 A	57.9	
2	LR1A	1	(4) #40	#30	2-1/2"	3	200 A	150 A	44.6	
3	SPARE	--	--	--	--	3	--	100 A	0.0	
4	SPARE	--	--	--	--	3	--	100 A	0.0	
5	SPARE	--	--	--	--	3	--	60 A	0.0	
6	SPARE	--	--	--	--	3	--	60 A	0.0	
7	SPD	--	--	--	--	3	--	50 A	0.0	
8	SPACE	--	--	--	--	--	--	--	0.0	
9	SPACE	--	--	--	--	--	--	--	0.0	
10	SPACE	--	--	--	--	--	--	--	0.0	
LOAD CLASSIFICATION		CONNECTED LOAD	DEMAND FACTOR	ESTIMATED DEMAND	PANEL TOTALS					
EQUIP		5000 VA	100.00%	5000 VA	TOTAL CONNECTED LOAD: 102 kVA					
HVAC		7900 VA	100.00%	7900 VA	TOTAL ESTIMATED DEMAND: 64 kVA					
REC		87280 VA	55.73%	48660 VA	TOTAL CONNECTED CURRENT: 284 A					
EQUIP - MISC		2000 VA	100.00%	2000 VA	TOTAL ESTIMATED DEMAND CURRENT: 176 A					

DISTRIBUTION PANELBOARD AND WIRING SCHEDULE										
SWITCHBOARD: LDP1B			MAINS TYPE: MCB			SCCR (KA): 10				
VOLTAGE: 208Y/120V/3P/4W			SPD: No			AVAIL FAULT CURRENT (KA): 5.8				
AMPERES: 400 A			MOUNTING: SURFACE			SUPPLY FROM: T-LDP1B				
CKT	CIRCUIT DESCRIPTION	SETS	WIRE	GND	COND	POLES	FRAME	TRIP	Load	REMARKS
1	LR1B	1	(4) #30	#3	2"	3	200 A	150 A	57.9	
2	LR1A	1	(4) #40	#30	2-1/2"	3	200 A	150 A	44.6	
3	SPARE	--	--	--	--	3	--	100 A	0.0	
4	SPARE	--	--	--	--	3	--	100 A	0.0	
5	SPARE	--	--	--	--	3	--	60 A	0.0	
6	SPARE	--	--	--	--	3	--	60 A	0.0	
7	SPD	--	--	--	--	3	--	50 A	0.0	
8	SPACE	--	--	--	--	--	--	--	0.0	
9	SPACE	--	--	--	--	--	--	--	0.0	
10	SPACE	--	--	--	--	--	--	--	0.0	
LOAD CLASSIFICATION		CONNECTED LOAD	DEMAND FACTOR	ESTIMATED DEMAND	PANEL TOTALS					
EQUIP		5000 VA	100.00%	5000 VA	TOTAL CONNECTED LOAD: 102 kVA					
HVAC		7900 VA	100.00%	7900 VA	TOTAL ESTIMATED DEMAND: 64 kVA					
REC		87280 VA	55.73%	48660 VA	TOTAL CONNECTED CURRENT: 284 A					
EQUIP - MISC		2000 VA	100.00%	2000 VA	TOTAL ESTIMATED DEMAND CURRENT: 176 A					

DISTRIBUTION PANELBOARD AND WIRING SCHEDULE										
SWITCHBOARD: LDP1B			MAINS TYPE: MCB			SCCR (KA): 10				
VOLTAGE: 208Y/120V/3P/4W			SPD: No			AVAIL FAULT CURRENT (KA): 5.8				
AMPERES: 400 A			MOUNTING: SURFACE			SUPPLY FROM: T-LDP1B				
CKT	CIRCUIT DESCRIPTION	SETS	WIRE	GND	COND	POLES	FRAME	TRIP	Load	REMARKS
1	LR1B	1	(4) #30	#3	2"	3	200 A	150 A	57.9	
2	LR1A	1	(4) #40	#30	2-1/2"	3	200 A	150 A	44.6	
3	SPARE	--	--	--	--	3	--	100 A	0.0	
4	SPARE	--	--	--	--	3	--	100 A	0.0	
5	SPARE	--	--	--	--	3	--	60 A	0.0	
6	SPARE	--	--	--	--	3	--	60 A	0.0	
7	SPD	--	--	--	--	3	--	50 A	0.0	
8	SPACE	--	--	--	--	--	--	--	0.0	
9	SPACE	--	--	--	--	--	--	--	0.0	
10	SPACE	--	--	--	--	--	--	--	0.0	
LOAD CLASSIFICATION		CONNECTED LOAD	DEMAND FACTOR	ESTIMATED DEMAND	PANEL TOTALS					
EQUIP		5000 VA	100.00%	5000 VA	TOTAL CONNECTED LOAD: 102 kVA					
HVAC		7900 VA	100.00%	7900 VA	TOTAL ESTIMATED DEMAND: 64 kVA					
REC		87280 VA	55.73%	48660 VA	TOTAL CONNECTED CURRENT: 284 A					
EQUIP - MISC		2000 VA	100.00%	2000 VA	TOTAL ESTIMATED DEMAND CURRENT: 176 A					

PANELBOARD AND WIRING SCHEDULE																	
PANEL: LR1A			MAINS TYPE: MCB			SCCR (KA): 10											
VOLTAGE: 208Y/120V/3P/4W			SPD: No			AVAIL FAULT CURRENT (KA): 3											
AMPERES: 150 A			MOUNTING: SURFACE			SUPPLY FROM: LDP1B											
CIRCUIT DESCRIPTION	N	WIRE	GND	C	OCF	P	DKT	A	B	C	OKT	PCP	C	GND	WIRE	N	CIRCUIT DESCRIPTION
REC - GEN ED SUPP 1331	20	1	1	0.9	1.1			0.7	0.9		2	1	20				REC - GEN ED SUPP 1331
REC - 1ST 1327	20	1	3								4	1	20				REC - 1ST 1327
REC - 1ST 1325	20	1	5							1.1	0.9	6	1	20			REC - 1ST 1325
REC - 1ST 1323	20	1	7	1.1	0.9						8	1	20				REC - 1ST 1323
REC - K 1337	20	1	9					0.7	1.1		10	1	20				REC - K 1337
REC - K 1315	20	1	11							1.1	0.7	12	1	20			REC - K 1315
REC - K 1313	20	1	13	1.1	0.7						14	1	20				REC - K 1313
REC - 1ST 1328	20	1	15					0.9	1.1		16	1	20				REC - 1ST 1328
REC - COMMONS 1ST 1300E	20	1	17					0.7	1.1		18	1	20				REC - 1ST 1324
REC - 1ST 1324	20	1	19	0.7	0.7						20	1	20				REC - SPEC ED 1322
REC - SPEC ED 1322	20	1	21					1.2	0.7		22	1	20				REC - K 1320
REC - K 1320	20	1	23							1.1	0.7	24	1	20			REC - COMMONS K 1300D
REC - K 1316	20	1	25	0.9	1.1						26	1	20				REC - K 1316
REC - SPEC ED 1314	20	1	27					0.7	2.1		28	1	20				REC - SPEC ED 1314
REC - CORRIDOR 1300	20	1	29						0.5	1.1	30	1	20				REC - CORRIDOR 1300
REC - CORRIDOR 1300	20	1	31	0.9	0.2						32	1	20				1 EWC - CORRIDOR 1300
REC - EXTERIOR AREA A	20	1	33					1.1	1.1		34	1	20				REC - EXTERIOR AREA A/B
REC - PLCKITCHEN 1307	20	1	35						0.5	1.5	36	1	20				1 FRIDGE - PLCKITCHEN 1307
SPACE	--	--	--	--	--	--	--	--	0.0	0.0	--	--	--	--	--	--	SPACE
SPACE	--	--	--	--	--	--	--	--	0.0	0.0	--	--	--	--	--	--	SPACE
SPACE	--	--	--	--	--	--	--	--	0.0	0.0	--	--	--	--	--	--	SPACE
VENDING - PLCKITCHEN 1307	20	1	43	1.0	1.0				0.1	1.5	44	1	20				1 VENDING - PLCKITCHEN 1307
COPIER - PLOKITCHEN 1307	20	2	45								46	1	20				REC - PLOKITCHEN 1307
REC - CORR 1300A	20	1	49	0.5	0.2						50	1	20				REC - CORR 1300A
SPARE	--	--	--	--	--	--	--	--	0.0	0.4	52	1	20				REC - CORR 1300C
REC - COMMONS K 1300D	20	1	51						0.5	0.7	54	1	20				REC - EXTERIOR AREA A/B
REC - ELEVATOR	20	1	55	0.2	0.7						56	1	20				EF-7 ELEC 1321
REC - COMMONS 1ST 1300E	20	1	57					0.5	0.5		58	1	20				EF-6 IT 1319
SEC-M IT 1319	20	1	59						0.5	0.0	60	1	20				SEC-C IT 1319
UH-1 K STOR 1406	20	2	63	1.2	0.0			1.2	0.0		64	1	20				SEC-M IT 1308
SPACE	--	--	--	--	--	--	--	--	0.0	0.0	66	1	20				SPACE
SPACE	--	--	--	--	--	--	--	--	0.0	0.0	68	1	20				SPACE
SPACE	--	--	--	--	--	--	--	--	0.0	0.0	70	1	20				SPACE
SPACE	--	--	--	--	--	--	--	--	0.0	0.0	72	1	20				SPACE
SPACE	--	--	--	--	--	--	--	--	0.0	0.0	74	1	20				SPACE
SPACE	--	--	--	--	--	--	--	--	0.0	0.0	76	1	20				SPACE
SPACE	--	--	--	--	--	--	--	--	0.0	0.0	78	1	20				SPACE
SPACE	--	--	--	--	--	--	--	--	0.0	0.0	80	1	20				SPACE
SPACE	--	--	--	--	--	--	--	--	0.0	0.0	82	1	20				SPACE
SPACE	--	--	--	--	--	--	--	--	0.0	0.0	84	1	20				SPACE
TOTAL LOAD (kVA):		14.7 kVA		16.8 kVA				13.2 kVA			TOTAL CURRENT (A):		124 A		142 A		110 A
LOAD CLASSIFICATION		CONNECTED LOAD	DEMAND FACTOR	ESTIMATED DEMAND	PANEL TOTALS												
EQUIP		2000 VA	100.00%	2000 VA	TOTAL CONNECTED LOAD: 45 kVA												
HVAC		3700 VA	100.00%	3700 VA	TOTAL ESTIMATED DEMAND: 31 kVA												
REC		37940 VA	63.8%	23970 VA	TOTAL CONNECTED CURRENT: 164 A												
EQUIP - MISC		1000 VA	100.00%	1000 VA	TOTAL ESTIMATED DEMAND CURRENT: 85 A												

PANELBOARD AND WIRING SCHEDULE																	
PANEL: LR2A			MAINS TYPE: MCB			SCCR (KA): 10											
VOLTAGE: 208Y/120V/3P/4W			SPD: No			AVAIL FAULT CURRENT (KA): 3.1											
AMPERES: 150 A			MOUNTING: SURFACE			SUPPLY FROM: LR2B											
CIRCUIT DESCRIPTION	N	WIRE	GND	C	OCF	P	DKT	A	B	C	OKT	PCP	C	GND	WIRE	N	CIRCUIT DESCRIPTION
REC - 2ND 2343	20	1	1	0.9	1.1						2	1	20				REC - 2ND 2343
REC - 2ND 2341	20	1	3					1.1	0.9		4	1	20				REC - 2ND 2341
REC - 2ND 2339	20	1	5							1.1	0.9	6	1	20			REC - 2ND 2339
REC - 3RD 2331	20	1	7	0.9	0.7						8	1	20				REC - 3RD 2331
REC - 3RD 2329	20	1	9					1.1	0.9		10	1	20				REC - 3RD 2329
REC - 3RD 2327	20	1	11							1.1	0.9	12	1	20			REC - 3RD 2327
REC - 2ND 2332	20	1	13	0.9	1.1						14	1	20				REC - 2ND 2332
REC - COMMONS 2ND 2300G	20	1	15					0.9	1.1		16	1	20				REC - 2ND 2328
REC - 2ND 2328	20	1	17							0.9	0.9	18	1	20			REC - GEN ED SUPP 2326
REC - GEN ED SUPP 2326	20	1	19	0.7	0.9						20	1	20				REC - 3RD 2324
REC - 3RD 2324	20	1	21					1.1	0.9		22	1	20				REC - COMMONS 3RD 2300F
REC - 3RD 2320	20	1	23							1.1	0.9	24	1	20			REC - 3RD 2320
REC - SPEC ED 2316A	20	1	25	0.9	1.0						26	1	20				REC - SPEC ED 2316A
REC - SPEC ED 2316B	20	1	27					1.0	0.7		28	1	20				REC - SPEC ED 2316B
REC - CART STORAGE 2325	20	1	29						0.5	0.7	30	1	20				REC - COMMONS 2ND 2300G
REC - COMMONS 3RD 2300F	20	1	31	0.9	0.5						32	1	20				REC - CUST 2349
REC - CORRIDOR 2300	20	1	33					1.3	0.5		34	1	20				1 EWC - CORRIDOR 2300
REC - CORRIDOR 2300	20	1	35							1.7	0.4	36	1	20			REC - CORRIDOR 2300C
EF-13A	20	1	37	0.2	0.7						38	1	20				EF-11
REC - ROOFTOP MAINT.	20	1	39					0.7	0.5		40	1	20				SEC-M IT 2333
EF-10	20	1	41								42	1	20				1 EWC - CORRIDOR 2300
SEC-C IT 2333	20	1	43	0.4	0.5												



THE LINE SHOWN ABOVE IS EXACTLY  
WHERE THE PANEL IS TO BE  
LOCATED. NO OTHER PANELS ARE TO BE

E

D

C

B

A

4/3/2024 4:07:20 PM

SWITCHBOARD AND WIRING SCHEDULE										
SWITCHBOARD: LDP1E			MAINS TYPE: MCB			SCCR (KA): 25				
VOLTAGE: 208Y120V,3P,4W			SPD: No			AVAIL FAULT CURRENT (KA): 8.6				
AMPERES: 800 A			MOUNTING: SURFACE			SUPPLY FROM: T-LDPIE				
CKT	CIRCUIT DESCRIPTION	SETS	WIRE	GND	COND	POLES	FRAME	TRIP	Load	REMARKS
1	LK	1	(4) #300 KCMIL	#1	2-1/2"	3	250 A	225 A	29.6	
2	UBS - KITCHEN 1202	1	(4) #300 KCMIL	#1	2-1/2"	3	250 A	225 A	23.9	
3	LR1C	1	(4) #30	#3	2"	3	200 A	150 A	23.6	
4	LR1E-1	1	(4) #300 KCMIL	#1	2-1/2"	3	250 A	225 A	48.3	
5	LR1E-2	1	(4) #30	#3	2"	3	200 A	150 A	35.0	
6	SPARE	--	--	--	--	3	--	100 A	0.0	
7	SPARE	--	--	--	--	3	--	100 A	0.0	
8	SPARE	--	--	--	--	3	--	50 A	0.0	
9	SPARE	--	--	--	--	3	--	50 A	0.0	
10	SPD	--	--	--	--	3	--	60 A	0.0	
LOAD CLASSIFICATION										
CONNECTED LOAD	DEMAND FACTOR	ESTIMATED DEMAND	PANEL TOTALS							
EQUIP 30460 VA	100.00%	30460 VA	TOTAL CONNECTED LOAD: 157 kVA							
HVAC 36442 VA	100.00%	36442 VA	TOTAL ESTIMATED DEMAND: 124 kVA							
KITCH 38880 VA	65.00%	25337 VA	TOTAL CONNECTED CURRENT: 434 A							
LTNG 627 VA	100.00%	627 VA	TOTAL ESTIMATED DEMAND CURRENT: 345 A							
REC 47524 VA	60.52%	28762 VA								
EQUIP - MISC 2500 VA	100.00%	2500 VA								
NOTES:										

PANELBOARD AND WIRING SCHEDULE																	
PANEL: LR1C			MAINS TYPE: MCB			SCCR (KA): 10											
VOLTAGE: 208Y120V,3P,4W			SPD: No			AVAIL FAULT CURRENT (KA): 2.9											
AMPERES: 150 A			MOUNTING: SURFACE			SUPPLY FROM: LDPIE											
CIRCUIT DESCRIPTION	N WIRE	GND	C	OC	P	CKT	A	B	C	CKT	P	OC	C	GND	WIRE	N	CIRCUIT DESCRIPTION
REC - MECH 1102	20	1	1	0.5	1.1	2	1	20		2	1	20					REC - CORRIDOR 1100
REC - CORRIDOR 1100	20	1	3				0.5	1.1		4	1	20					REC - MEDIA WKRM 1101A
REC - MEDIA WKRM 1101A	20	1	5						0.9	0.9	6	1	20				REC - AV EQUIP STORAGE
REC - MEDIA CENTER 1101	20	1	7	1.1	0.7						8	1	20				REC - MEDIA CENTER 1101
REC - COLLAB 1101D	20	1	9				1.1	0.7			10	1	20				REC - MEDIA CENTER 1101
REC - MEDIA CENTER 1101	20	1	11						0.7	1.1	12	1	20				REC - COLLAB 1101D
REC - MEDIA CENTER 1101	20	1	13	1.4	0.4						14	1	20				REC - WP
REC - MEDIA CENTER 1101	20	1	15				0.7	0.7			16	1	20				REC - MEDIA CENTER 1101
EF-3	20	1	17						1.0	0.2	18	1	20				VAV CONTROL PANELS
TOP	20	1	19	0.5	0.2						20	1	20				VAV CONTROL PANELS
SEC-C H.E.INDF 1103	20	1	21				0.5	0.2			22	1	20				VAV CONTROL PANELS
SEC-C HEAD END/INDF 1103	20	1	23						0.5	1.0	24	1	20				POWER SHADES - MEDIA 1101
SEC-P HEAD END/INDF 1103	20	1	25	0.5	1.0						26	1	20				POWER SHADES - MEDIA 1101
POWER SHADES - MEDIA 1101	20	1	27				0.0	1.1			28	1	20				REC - MEDIA CENTER 1101
SPARE	20	2	29				1.2	1.1			30	1	20				REC - MEDIA CENTER 1101
UH-1 MECH 1102	20	1	31	1.2	0.0						32	1	20				SPARE
SPARE	20	1	33				0.0	0.0			34	1	20				SPARE
SPARE	20	1	35				0.0	0.0			36	1	20				SPARE
SPARE	20	1	37	0.0	0.0						38	1	20				SPARE
SPARE	20	1	39				0.0	0.0			40	1	20				SPARE
SPARE	20	1	41				0.0	0.0			42	1	20				SPARE
SPARE	20	1	43	0.0	0.0						44	1	20				SPARE
SPARE	20	1	45				0.0	0.0			46	1	20				SPARE
SPARE	20	1	47				0.0	0.0			48	1	20				SPARE
SPARE	20	1	49	0.0	0.0						50	1	20				SPARE
SPARE	20	1	51				0.0	0.0			52	1	20				SPARE
SPARE	20	1	53				0.0	0.0			54	1	20				SPARE
SPARE	20	1	55	0.0	0.0						56	1	20				SPARE
SPARE	20	1	57				0.0	0.0			58	1	20				SPARE
SPARE	20	1	59				0.0	0.0			60	1	20				SPARE
LOAD CLASSIFICATION																	
CONNECTED LOAD	DEMAND FACTOR	ESTIMATED DEMAND	PANEL TOTALS														
EQUIP 3000 VA	100.00%	3000 VA	TOTAL CONNECTED LOAD: 24 kVA														
HVAC 4540 VA	100.00%	4540 VA	TOTAL ESTIMATED DEMAND: 21 kVA														
REC 14580 VA	94.29%	12290 VA	TOTAL CONNECTED CURRENT: 86 A														
EQUIP - MISC 1500 VA	100.00%	1500 VA	TOTAL ESTIMATED DEMAND CURRENT: 59 A														
NOTES:																	

PANELBOARD AND WIRING SCHEDULE																	
PANEL: LR1E-1			MAINS TYPE: MLO			SCCR (KA): 10											
VOLTAGE: 208Y120V,3P,4W			SPD: No			AVAIL FAULT CURRENT (KA): 7.0											
AMPERES: 225 A			MOUNTING: SURFACE			SUPPLY FROM: LDPIE											
CIRCUIT DESCRIPTION	N WIRE	GND	C	OC	P	CKT	A	B	C	CKT	P	OC	C	GND	WIRE	N	CIRCUIT DESCRIPTION
REC - CLASSROOM 1104	20	1	1	0.9	0.9					2	1	20					REC - CLASSROOM 1104
REC - COMMONS 1100B	20	1	3				1.1	0.4			4	1	20				REC - ART 1106
REC - ART 1106	20	1	5						0.7	0.7	6	1	20				REC - ART 1106
REC - RAIP 1105A	20	1	7	0.7	0.9						8	1	20				REC - PLATFORM 1105B
REC - CHR STO / DRESS 1105C	20	1	9				0.4	1.1			10	1	20				REC - PLAY 1105
REC - KILN 1106B	20	1	11						0.7	0.9	12	1	20				REC - MUSIC 1108
REC - MUSIC 1108	20	1	13	0.9	0.9						14	1	20				REC - PE OFF 1109F
REC - PE STO 1109E	20	1	15				0.4	1.1			16	1	20				REC - RECEIVING 1203
REC - CUST 1203C	20	1	17						0.4	1.1	18	1	20				REC - MNG OFF 1203D
REC - DINING 1201	20	1	19	0.9	0.7						20	1	20				REC - DINING 1201
REC - CORRIDOR 1100	20	1	21				0.5	0.5			22	1	20				REC - CORRIDOR 1100
REC - ELEC 1401	20	1	23						0.7	0.9	24	1	20				REC - CORRIDOR 1100
EF-1 IT 1203A	20	1	25	0.7	0.7						26	1	20				EF-2 KILN 1106B
REC - EXTERIOR	20	1	27				1.1	0.5			28	1	20				REC - EXTERIOR
REC - EXTERIOR	20	1	29						0.7	0.9	30	1	20				REC - EXTERIOR
REC - RESTROOMS	20	1	31	0.4	0.5						32	1	20				PROJECTOR - PLATFORM
MOTOR SCREEN - PLATFORM	20	1	33				0.5	1.1			34	1	20				REC - DINING 1201
SCOREBOARD - PLAY 1105	20	1	35						0.5	0.5	36	1	20				REC - DINING ROOM
GOAL BACKBOARD - 1105	20	1	37	1.0	1.5						38	1	20				POWER SHADES - DINING 1201
GOAL BACKBOARD - 1105	20	1	39				1.0	0.7			40	1	20				REC-KILN FAN
GOAL BACKBOARD - 1105	20	1	41						1.0	3.7	42						
GOAL BACKBOARD - 1105	20	1	43	1.0	3.7						44	3	40	34"	#10	#8	KILN
REC - PLATFORM 1105B	20	1	45				0.4	3.7			46						
PLATFORM LTG	20	1	47						0.3	0.5	48	1	20				SEC-M IT 1203A
PLATFORM LTG	20	1	49	0.2	0.5						50	1	20				SEC-C IT 1203A
PLATFORM LTG	20	1	51				0.2	0.4			52	1	20				REC - ART 1106
SOUND EQUIPMENT	20	1	53						0.4	1.0	54	1	20				CONTACTOR CABINET
SOUND EQUIPMENT	20	1	55	0.4	1.0						56	1	20				CONTACTOR CABINET
PRESET STATION	20	1	57				0.2	0.0			58	1	20				SPARE
EQUIP	20	1	59				0.5	0.0			60	1	20				SPARE
SPARE	20	1	61	0.0	0.0						62	1	20				SPARE
SPARE	20	1	63				0.0	0.0			64	1	20				SPARE
SPARE	20	1	65						0.0	0.0	66	1	20				SPARE
SPARE	20	1	67	0.0	0.0						68	1	20				SPARE
SPARE	20	1	69				0.0	0.0			70	1	20				SPARE
SPARE	20	1	71						0.0	0.0	72	1	20				SPARE
SPARE	20	1	73	0.0	0.0						74	1	20				SPARE
SPARE	20	1	75				0.0	0.0			76	1	20				SPARE
SPARE	20	1	77						0.0	0.0	78	1	20				SPARE
SPARE	20	1	79	0.0	0.0						80	1	20				SPARE
SPARE	20	1	81				0.0	0.0			82	1	20				SPARE
SPARE	20	1	83				0.0	0.0			84	1	20				SPARE
LOAD CLASSIFICATION																	
CONNECTED LOAD	DEMAND FACTOR	ESTIMATED DEMAND	PANEL TOTALS														
EQUIP 2020 VA	100.00%	2020 VA	TOTAL CONNECTED LOAD: 47 kVA														
HVAC 1400 VA	100.00%	1400 VA	TOTAL ESTIMATED DEMAND: 40 kVA														
KITCH 180 VA	100.00%	180 VA	TOTAL CONNECTED CURRENT: 131 A														
LTNG 627 VA	100.00%	627 VA	TOTAL ESTIMATED DEMAND CURRENT: 112 A														
REC 23920 VA	70.90%	16960 VA															
EQUIP - MISC 1000 VA	100.00%	1000 VA															
NOTES:																	

PANELBOARD AND WIRING SCHEDULE																	
PANEL: LR1E-2			MAINS TYPE: MLO			SCCR (KA): 10											
VOLTAGE: 208Y120V,3P,4W			SPD: No			AVAIL FAULT CURRENT (KA): 7.0											
AMPERES: 150 A			MOUNTING: SURFACE			SUPPLY FROM: LDPIE											
CIRCUIT DESCRIPTION	N WIRE	GND	C	OC	P	CKT	A	B	C	CKT	P	OC	C	GND	WIRE	N	CIRCUIT DESCRIPTION
UH-1 EMERG EL 1401A	20	2	1	1.2	2.0					2	2	30	34"	#10	#10		UH-2 ELEC 1401
UH-2 - BOILER 1403	#10	#10	34"	30	2	5				2.0	1.0	6	1	20			BAS PANELS - BOILER 1403
BOILER-2						7	2.0	1.6			8	1</					



PANELBOARD AND WIRING SCHEDULE																
PANEL: EMH1				MAINS TYPE: MLO				SCCR (KA): 18								
VOLTAGE: 480Y/277V, 3P, 4W				SPD: Yes				AVAIL FAULT CURRENT (KA): 10								
AMPERES: 100 A				MOUNTING: SURFACE				SUPPLY FROM: EMATS								
CIRCUIT DESCRIPTION	WIRE	GND	C	OC	P	CKT	A	B	C	CKT	P	OC	C	GND	WIRE	CIRCUIT DESCRIPTION
T-EMH1	(3) #6	#10	1"	50	3	3	3.4	3.5		2	3	60	1-1/4"	#8	(4) #4	EMH1B
EM LING - 1ST AREA A							4.8	3.8		8	1	20				EM LING - COORIDOR 1100
EM LING - 1ST AREA C							2.6	1.1		10	1	20				EM LING - EXTERIOR
EM LING - 1ST AREA D							2.1	0.7		0.0	0.0	12	1	20		SPARE
SPARE							0.0	0.0		14	1	20				SPARE
SPARE							0.0	0.0		16	1	20				SPARE
SPARE							0.0	0.0		18	1	20				SPARE
SPARE							0.0	0.0		20	1	20				SPARE
SPARE							0.0	0.0		22	1	20				SPARE
SPARE							0.0	0.0		24	1	20				SPARE
SPARE							0.0	0.0		26	3	30				SPD
SPARE							0.0	0.0		28	3	30				SPD
SPARE							0.0	0.0		30	3	30				SPD
TOTAL LOAD (KVA):				10.6 KVA				11.4 KVA				4.4 KVA				
TOTAL CURRENT (A):				42 A				45 A				16 A				
LOAD CLASSIFICATION																
CONNECTED LOAD	DEMAND FACTOR	ESTIMATED DEMAND	PANEL TOTALS													
EQUIP	5300 VA	100.00%	5300 VA	TOTAL CONNECTED LOAD: 25 KVA												
LTNG	1447 VA	100.00%	1447 VA	TOTAL ESTIMATED DEMAND: 25 KVA												
REC	720 VA	100.00%	720 VA	TOTAL CONNECTED CURRENT: 31 A												
EQUIP - MISC	5000 VA	100.00%	5000 VA	TOTAL ESTIMATED DEMAND CURRENT: 31 A												

PANELBOARD AND WIRING SCHEDULE																
PANEL: EMH1B				MAINS TYPE: MCB				SCCR (KA): 18								
VOLTAGE: 480Y/277V, 3P, 4W				SPD: Yes				AVAIL FAULT CURRENT (KA): 1.7								
AMPERES: 60 A				MOUNTING: SURFACE				SUPPLY FROM: EMH1								
CIRCUIT DESCRIPTION	WIRE	GND	C	OC	P	CKT	A	B	C	CKT	P	OC	C	GND	WIRE	CIRCUIT DESCRIPTION
EM LING - 1ST AREA A							2	1		2	1	20				EM LING - 1ST AREA B
EM LING - 1ST AREA C							0.6	1.6		4	1	20				EM LING - EXTERIOR
EM LING - EXT AREA A/B/C							0.5	0.0		6	1	20				SPARE
SPARE							0.0	0.0		8	1	20				SPARE
SPARE							0.0	0.0		10	1	20				SPARE
SPARE							0.0	0.0		12	1	20				SPARE
SPARE							0.0	0.0		14	1	20				SPARE
SPARE							0.0	0.0		16	1	20				SPARE
SPARE							0.0	0.0		18	1	20				SPARE
SPARE							0.0	0.0		20	1	20				SPARE
SPARE							0.0	0.0		22	1	20				SPARE
SPARE							0.0	0.0		24	1	20				SPARE
SPARE							0.0	0.0		26	3	30				SPD
SPARE							0.0	0.0		28	3	30				SPD
SPARE							0.0	0.0		30	3	30				SPD
TOTAL LOAD (KVA):				3.5 KVA				3.8 KVA				0.5 KVA				
TOTAL CURRENT (A):				14 A				16 A				7 A				
LOAD CLASSIFICATION																
CONNECTED LOAD	DEMAND FACTOR	ESTIMATED DEMAND	PANEL TOTALS													
LTNG	7870 VA	100.00%	7870 VA	TOTAL CONNECTED LOAD: 8 KVA												
			TOTAL ESTIMATED DEMAND: 8 KVA													
			TOTAL CONNECTED CURRENT: 9 A													
			TOTAL ESTIMATED DEMAND CURRENT: 9 A													

PANELBOARD AND WIRING SCHEDULE																
PANEL: EMH2B				MAINS TYPE: MCB				SCCR (KA): 18								
VOLTAGE: 480Y/277V, 3P, 4W				SPD: Yes				AVAIL FAULT CURRENT (KA): 1.5								
AMPERES: 60 A				MOUNTING: SURFACE				SUPPLY FROM: EMH1B								
CIRCUIT DESCRIPTION	WIRE	GND	C	OC	P	CKT	A	B	C	CKT	P	OC	C	GND	WIRE	CIRCUIT DESCRIPTION
EM LING - 2ND AREA A/B							1.5	0.0		2	1	20				SPARE
EM LING - 2ND AREA B/C							1.7	0.0		4	1	20				SPARE
SPARE							0.0	0.0		6	1	20				SPARE
SPARE							0.0	0.0		8	1	20				SPARE
SPARE							0.0	0.0		10	1	20				SPARE
SPARE							0.0	0.0		12	1	20				SPARE
SPARE							0.0	0.0		14	1	20				SPARE
SPARE							0.0	0.0		16	1	20				SPARE
SPARE							0.0	0.0		18	1	20				SPARE
SPARE							0.0	0.0		20	1	20				SPARE
SPARE							0.0	0.0		22	1	20				SPARE
SPARE							0.0	0.0		24	1	20				SPARE
SPARE							0.0	0.0		26	1	20				SPARE
SPARE							0.0	0.0		28	1	20				SPARE
SPARE							0.0	0.0		30	1	20				SPARE
TOTAL LOAD (KVA):				1.5 KVA				1.7 KVA				0.0 KVA				
TOTAL CURRENT (A):				6 A				7 A				0 A				
LOAD CLASSIFICATION																
CONNECTED LOAD	DEMAND FACTOR	ESTIMATED DEMAND	PANEL TOTALS													
LTNG	3203 VA	100.00%	3203 VA	TOTAL CONNECTED LOAD: 3 KVA												
			TOTAL ESTIMATED DEMAND: 3 KVA													
			TOTAL CONNECTED CURRENT: 4 A													
			TOTAL ESTIMATED DEMAND CURRENT: 4 A													

PANELBOARD AND WIRING SCHEDULE																
PANEL: EML1				MAINS TYPE: MCB				SCCR (KA): 10								
VOLTAGE: 208Y/120V, 3P, 4W				SPD: Yes				AVAIL FAULT CURRENT (KA): 1.8								
AMPERES: 100 A				MOUNTING: SURFACE				SUPPLY FROM: T-SBL1								
CIRCUIT DESCRIPTION	WIRE	GND	C	OC	P	CKT	A	B	C	CKT	P	OC	C	GND	WIRE	CIRCUIT DESCRIPTION
NAC PANEL - ELEC 1401							0.5	0.5		2	1	20				NAC PANEL - ELEC 1321
FACP - ELEC 1401							0.5	0.5		4	1	20				NAC PANEL - ELEC 1310
TRAN - HEAD END/MDF 1103							0.5	0.5		6	1	20				FAAM - RESEP. 1001
FAA - ENTRY VEST 1100A							0.2	0.2		8	1	20				REC - GDS
BDA EQUIPMENT							0.4	0.2		10	1	20				GEN LIGHTING
REC - GDS							0.1	0.1		12	2	20				GEN HEATER
GEN BATTERY CHARGER							0.1	0.1		14	1	20				GEN ANN
GEN CONTROLS							0.2	1.0		16	1	20				DOOR POWER - IT 1203A
SECA IT 1203A							0.5	0.5		18	1	20				DOOR POWER - H.E.A.MDF 1103
SECA HEAD END/MDF 1103							0.5	0.5		20	1	20				DOOR POWER - IT 1319
SECC IT 1319							0.5	0.5		22	1	20				DOOR POWER - IT 1389
SECA IT 1308							0.5	0.5		24	1	20				DOOR POWER - IT 2333
SECA IT 2333							0.5	0.5		26	1	20				DOOR POWER - IT 2312
SECA IT 2312							0.5	0.5		28	1	20				TWO WAY COMM
SPARE							0.0	0.0		30	1	20				SPARE
SPARE							0.0	0.0		32	1	20				SPARE
SPARE							0.0	0.0		34	1	20				SPARE
SPARE							0.0	0.0		36	1	20				SPARE
SPARE							0.0	0.0		38	1	20				SPARE
SPARE							0.0	0.0		40	3	30				SPD
SPARE							0.0	0.0		42	3	30				SPD
TOTAL LOAD (KVA):				3.4 KVA				4.8 KVA				3.9 KVA				
TOTAL CURRENT (A):				28 A				40 A				33 A				
LOAD CLASSIFICATION																
CONNECTED LOAD	DEMAND FACTOR	ESTIMATED DEMAND	PANEL TOTALS													
EQUIP	5300 VA	100.00%	5300 VA	TOTAL CONNECTED LOAD: 11 KVA												
REC	720 VA	100.00%	720 VA	TOTAL ESTIMATED DEMAND: 11 KVA												
EQUIP - MISC	5000 VA	100.00%	5000 VA	TOTAL CONNECTED CURRENT: 31 A												
			TOTAL ESTIMATED DEMAND CURRENT: 31 A													

PANELBOARD AND WIRING SCHEDULE																
PANEL: SBH1				MAINS TYPE: MLO				SCCR (KA): 18								
VOLTAGE: 480Y/277V, 3P, 4W				SPD: Yes				AVAIL FAULT CURRENT (KA): 1.7								
AMPERES: 200 A				MOUNTING: SURFACE				SUPPLY FROM: SBATS								
CIRCUIT DESCRIPTION	WIRE	GND	C	OC	P	CKT	A	B	C	CKT	P	OC	C	GND	WIRE	CIRCUIT DESCRIPTION
T-SBL1E	(3) #6	#10	1"	50	3	3	7.2	5.0		2	3	50	1-1/4"	#6	(3) #3	T-SBL1A
ELEVATOR	(3) #6	#8	1-1/4"	60	3	9	3.9	0.0		7	3	9				SPARE
SPARE							0.0	0.0		9	3	9				SPARE
SPARE							0.0	0.0		11	3	9				SPARE
SPARE							0.0	0.0		13	0.0	0.0				SPARE
SPARE							0.0	0.0		15	0.0	0.0				SPARE
SPARE							0.0	0.0		17	0.0	0.0				SPARE
SPARE							0.0	0.								